BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work : Repairs and maintenance to existing borewells in ward no. 8, kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	11	Lifting of Submersible pump set as per Soecification and direction etc complete as per specifications and directions of engineer in charge of the work	Each	850.00	
2	11	Transportation of pumping machineries etc complete as per specifications and directions of engineer in charge of the work	Each	900.00	
3	11	Labour charges (over hauling) etc complete as per specifications and directions of engineer in charge of the work	Job	550.00	
4	5	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. **(Above 10 HP upto 20 HP add Rs.150/- for every ½ HP) up to 10 HP** etc complete as per specifications and directions of engineer in charge of the work		3700.00	
4A	6	12.5 HP		4750.00	
5	11	Starter (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	5050.00	
6	11	Rotor (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	4700.00	
7	11	Upper Flange etc complete as per specifications and directions of engineer in charge of the work	No.	350.00	
8	11	Lower Housing etc complete as per specifications and directions of engineer in charge of the work	No.	650.00	
9	11	Carbon Housing etc complete as per specifications and directions of engineer in charge of the work	No.	475.00	
10	11	Thrust bearing block assembly complete with Segment bearing pad etc complete as per specifications and directions of engineer in charge of the work	No.	1150.00	
11	11	Oil Seal etc complete as per specifications and directions of engineer in charge of the work	No.	125.00	

Sl. No.	Quantity.	Description	Unit	Rates In Figures	Rates In Words
12	11	Oil Seal Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	150.00	
13	165	Guide vane etc complete as per specifications and directions of engineer in charge of the work	No.	175.00	
14	165	Impeller Shell moulded with aluminium Bronze) etc complete as per specifications and directions of engineer in charge of the work	No.	425.00	
15	11	Discharge outlet (D.O) Bearing D.O Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	445.00	
16	11	Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	150.00	
17	11	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc complete as per specifications and directions of engineer in charge of the work	No.	950.00	
18	11	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc complete as per specifications and directions of engineer in charge of the work	No.	1350.00	
19	11	Cable Guard etc complete as per specifications and directions of engineer in charge of the work	No.	150.00	
20	11	Brass Filter etc complete as per specifications and directions of engineer in charge of the work	No.	250.00	
21	11	Re-erection charges of pumping machineries including overhauling and pointing etc complete as per specifications and directions of engineer in charge of the work	Each	950.00	
22	260.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) **4 Sqm mm of 56 strands 0.3mm dia Group - A** etc complete as per specifications and directions of engineer in charge of the work	Mtr	151.00	

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore - 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
24/12/15